

MARKET HOME
283 ELI'S PASS

PLOT PLAN

LOT 53 - 0.9568 AC.

THE ESTATES OF KEEVER


CREEK, SEC 3

SECTION 23, TOWN 4, RANGE 3

TURTLECREEK TWP, WARREN

CO., OHIO

FOR: CRISTO HOMES



QUANTITIES

- TOTAL LOT AREA=41,678 SF
- CITY WALK=X
- HOUSE WALK=31.0 SF
- DRIVE=1434.8 SF
- APRON=93.0 SF
- PATIO & PORCHES=78.7 SF
- DECK=X
- SEEDING=18,515 SF
- SOD=X
- UNSEEDED=21,984 SF

INFORMATION FROM CONSTRUCTION DRAWINGS.

CONTRACTOR IS TO VERIFY LOCATION AND DEPTH OF WATER AND UTILITY SERVICES BEFORE CONSTRUCTION.

ALL ELEVATIONS ARE EXISTING UNLESS SPECIFIED WITH AN "E" FOR EXISTING OR A "P" FOR PROPOSED.

UNLESS F.F.E., M.O.E. OR M.B.E. ARE FIELD VERIFIED BY AN ENGINEERING FIRM, CONTRACTOR TAKES FULL RESPONSIBILITY FOR THE FINISH FLOOR ELEVATION.

A STANDARD FORMULA WAS USED TO DETERMINE FINISH FLOOR GRADE. FINAL FINISH FLOOR ELEVATION IS CONTRACTOR'S RESPONSIBILITY.

Prior to construction, a geotechnical report shall be obtained by the builder. Apex assumes no responsibility for soil conditions.

BUILDER SHALL PROVIDE POSITIVE DRAINAGE AROUND AND AWAY FROM HOUSES.

APEX ENGINEERING & SURVEYING INC. ADVISES AGAINST HOLDING THE MINIMUM REQUIRED DISTANCE ON ANY AND ALL SETBACKS, FRONT, REAR, AND SIDES. THE BUILDER ASSUMES ALL RESPONSIBILITIES FOR ANY BUILDING ENCROACHMENTS THAT MAY OCCUR.

C6
R=2530.00'
L=130.96'

SETBACKS
FRONT=50'
REAR=35'
SIDE=5' / 20' TOTAL




TOPOGRAPHY FROM CONSTRUCTION PLANS, DATED JUNE, 2016 AND MAY NOT REFLECT CURRENT CONDITIONS.

SCALE: 1"=30'
 DATE: 11-09-18
 DRAWN: JLL
 DESIGNED:
 CHECKED: KRC

APEX
 ENGINEERING & SURVEYING, INC.
 1068 N. UNIVERSITY BLVD MIDDLETOWN, OHIO 45042
 PH.-(513) 424-5202 OR (513) 932-8991 FAX - (513) 424-6202

REVISIONS:
 1.
 2.
 3.
 4.

PROJECT: KEEVERCREEK DRAWING: 182000PA	SHEET 1 OF 1
---	-----------------



SECOND FLOOR PLAN
SCALE: 1/8" = 1'-0" 1531 S.F.

Second Floor Plan - Traditional

A4